



ABBREVIATIONS

- CB CHALKBOARD
- MB MARKERBOARD
- SMTBD SMARTBOARD
- VDB VISUAL DISPLAY MONITOR
- MVDM MOBILE VISUAL DISPLAY MONITOR
- TB TACK BOARD
- BK BOOKCASE
- CU CUBBIES
- IABW INTERACTIVE WHITE BOARD
- FSTV FLAT SCREEN T.V.
- MT METAL THRESHOLD W/ 1/2" MAX. LIP
- RT RUBBER TRANSITION W/ 1/2" MAX. LIP
- FEC FIRE EXTINGUISHER CABINET
- C.J. CONTROL JOINT
- E.J. EXPANSION JOINT
- TD TRAVEL DISTANCE
- SEE SHEET T-1 FOR ADDITIONAL ABBREVIATIONS

WALL LEGEND

- 12" CMU WALL
- 10" CMU WALL
- 8" CMU WALL
- 6" CMU WALL
- 6" METAL STUD WALL WITH GYPSOBOARD EACH SIDE WITH SOUND ATTENUATION BATTS
- 3 5/8" METAL STUD WALL WITH GYPSOBOARD EACH SIDE WITH SOUND ATTENUATION BATTS
- ONE HOUR RATED FIRE BARRIER
- TWO HOUR RATED FIRE WALL
- SMOKE TIGHT CONSTRUCTION WALLS

ROOM FINISH SCHEDULE

| MARK | AREA | FLOOR | BASE | WALLS | CEILING | CLG HEIGHT | REMARKS |
|-------|--------------------|--------------|-----------|----------------------|---------------------|------------|---|
| 511 | PEDESTRIAN WALKWAY | TERRAZZO | 4" RUBBER | PAINTED CMU | ACOUSTICAL TILE | 10'-0" | |
| 512 A | CORRIDOR | TERRAZZO | 4" RUBBER | PAINTED CMU | ACOUSTICAL TILE | 10'-0" | |
| 512 B | STAFF TOILET | CER TILE | CER TILE | PAINT CMU / CER TILE | ACOUSTICAL TILE | 9'-0" | |
| 512 C | STAFF TOILET | CER TILE | CER TILE | PAINT CMU / CER TILE | ACOUSTICAL TILE | 9'-0" | |
| 512 D | CUSTODIAN | CER TILE | CER TILE | PAINTED CMU | PNT M.R. GYPSOBOARD | 10'-0" | |
| 512 E | ACCESS | SEALED CONC. | NONE | NONE | EXPOSED STRUCTURE | VARIES | |
| 513 A | SCIENCE CLASSROOM | VCT | 4" RUBBER | PAINTED CMU | ACOUSTICAL TILE | 10'-0" | SMOKE TIGHT GYPBD. CEILING ABOVE ACT PER PLAN |
| 513 B | PREP | VCT | 4" RUBBER | PAINTED CMU | ACOUSTICAL TILE | 10'-0" | SMOKE TIGHT GYPBD. CEILING ABOVE ACT PER PLAN |
| 513 C | CHEMICAL STORAGE | VCT | 4" RUBBER | PAINTED CMU | ACOUSTICAL TILE | 10'-0" | SMOKE TIGHT GYPBD. CEILING ABOVE ACT PER PLAN |
| 514 A | SCIENCE CLASSROOM | VCT | 4" RUBBER | PAINTED CMU | ACOUSTICAL TILE | 10'-0" | SMOKE TIGHT GYPBD. CEILING ABOVE ACT PER PLAN |
| 514 B | PREP | VCT | 4" RUBBER | PAINTED CMU | ACOUSTICAL TILE | 10'-0" | SMOKE TIGHT GYPBD. CEILING ABOVE ACT PER PLAN |
| 514 C | CHEMICAL STORAGE | VCT | 4" RUBBER | PAINTED CMU | ACOUSTICAL TILE | 10'-0" | SMOKE TIGHT GYPBD. CEILING ABOVE ACT PER PLAN |
| 515 | SCIENCE CLASSROOM | VCT | 4" RUBBER | PAINTED CMU | ACOUSTICAL TILE | 10'-0" | SMOKE TIGHT GYPBD. CEILING ABOVE ACT PER PLAN |
| 516 | SCIENCE CLASSROOM | VCT | 4" RUBBER | PAINTED CMU | ACOUSTICAL TILE | 10'-0" | SMOKE TIGHT GYPBD. CEILING ABOVE ACT PER PLAN |
| 517 | WOMEN | CER TILE | CER TILE | PAINTED / CER TILE | PNT M.R. GYPSOBOARD | 10'-0" | |
| 518 | MEN | CER TILE | CER TILE | PAINTED / CER TILE | PNT M.R. GYPSOBOARD | 10'-0" | |
| 519 | ROTC | VCT | 4" RUBBER | PAINTED CMU | ACOUSTICAL TILE | 10'-0" | |
| 520 A | ROTC | VCT | 4" RUBBER | PAINTED CMU | ACOUSTICAL TILE | 10'-0" | |
| 520 B | OFFICE | VCT | 4" RUBBER | PAINTED CMU | ACOUSTICAL TILE | 9'-0" | |
| 520 C | ARMORY | VCT | 4" RUBBER | PAINTED CMU | ACOUSTICAL TILE | 10'-0" | |
| 521 | SPRINKLER RISER | SEALED CONC. | NONE | NONE | PNT M.R. GYPSOBOARD | 10'-0" | |
| 522 A | EQUIP. PLATFORM | SEALED CONC. | NONE | NONE | EXPOSED STRUCTURE | VARIES | |
| 522 B | IDF | VCT | 4" RUBBER | PAINTED DRYWALL | ACOUSTICAL TILE | 8'-0" | |

- OVERHEAD PLATFORM AND ACCESS AREAS: PAINT STEEL STAIRS AND RAILS AS SPECIFIED AND PROVIDE (2) COATS GLOSS POLYURETHANE FLOOR SEALER AS SPECIFIED FOLLOWING FINAL
- GYPSOBOARD CEILINGS AND BULKHEADS: PAINT FLAT WHITE LATEX, NO TEXTURE, USE STRAIGHT CORNER BEADS, NO BULLNOSE EXCEPT WHERE INDICATED

| | |
|-----|-------------------------|
| No. | Date |
| 1 | 11-16-23 |
| 2 | Revised per Addendum #3 |
| 3 | |
| 4 | |
| 5 | |
| 6 | |
| 7 | |
| 8 | |
| 9 | |
| 10 | |

Hite associates
ARCHITECTURE / PLANNING / TECHNOLOGY
2600 Meridian Drive / Greenville, NC 27834 / Tel(252) 757-0333

REGISTERED ARCHITECT
418
JAMES GRAY HITE
GREENVILLE, NC

New Gymnasium Additions to
West Carteret High School
4700 Country Club Road, Morehead City, NC 28577
Carteret County Schools / North Carolina

Project No: 22112
Date: 18 August 2022
Drawing No: **A 501**